

Solar Layout: Canon Del Sol HOA SN15015

Project Status:	Approved
Preliminary Estimated Year 1 PV Output:	31,173 kWh
Estimated Yearly Usage:	35,000 kWh
Roof:	Good condition.
Electrical:	Install solar sub panel on the exterior wall next to the main panel.
Shade:	Average 99% Solar Access
Additional Services and/or Battery:	NEM Aggregation



Equipment

PV Module	55	LG Electronics LG370N1K-A6
Inverters	55	Enphase Energy IQ7A-72-2-US [240V]

Rating 20.350 kW STC / 18.860 kW PTC / 18.294 kW CEC